Abstract estimate for constructing a Police Station at Bhadravati with compound wall and a set of Latrines.

No.	Items of work	Unit	Rate	Quantity	Rate in words
			Rs. a. p.		
1	Clearing site and levelling ground	L. S.	..	..	
2	Earthwork excavation and using the earth for filling in basement	C.yds.	0 4 0	109	
3	Stone jelly concrete in lime mortar 1 : 2 : 4 ..	C.ft.	0 4 6	987	
4	Size stone in mortar	,,	0 5 0	1,665	
5	Burnt brick in mortar	,,	0 4 6	2,545	
6	Burnt stone slabs 6″ thick roughly dressed ..	S.ft.	0 12 0	653	
7	Teakwood battened doors with $3\frac{1}{2}''\times5''$ frames with C. I. ventilators at top $1\frac{1}{4}''$ thick planks complete with fittings wooden stoppers, etc.	,,	1 10 0	125	
8	T.W. battened windows with $\frac{3}{4}''$ iron bars and fittings and including C. I. ventilators at top and shutters complete	,,	1 14 0	132	
9	T.W. lock-up doors as per type design $4'\times7'$ with iron bars and inspection opening and fixing to wall with bolts and nuts ..	,,	2 0 0	39	
10	T.W. hit and miss ventilators with fixing, etc., as per design	,,	1 10 0	$31\frac{1}{2}$	
11	R. C. ventilators in the hall as per design ..	,,	1 8 0	45	
12	Chunam plastering	Sqr.	3 8 0	54.69	
13	White-washing, 2 coats	,,	0 4 6	54.69	
14	R.B.C. terraced roofing as per specifications to be approved by the Executive Engineer with cornice projection	,,	65 0 0	13.77	
15	R. C. Chajja 4″ thick verandah including 1′ anchoring in the wall on windows ..	S.ft.	0 10 0	287	
16	Flooring with 4″ chunam concrete with $1\frac{1}{2}''$ cement concrete and plastered over with $\frac{1}{2}''$ cement plaster and finished with red colour	Sqr.	20 0 0	11·35	
17	Constructing $1\frac{1}{2}'$ parapet complete with base and top beading wall 9″ thick	R.ft.	0 8 0	230	
18	Providing and fixing rolled steel joists ..	Cwt.	12 0 0	39.7	
19	Boxing girders with cement concrete ..	R.ft.	1 0 0	52	
20	Forming letters of name board and fixing date stone on the top of the main room terrace	L. S.			
21	Improving the front elevation with stucco ..	,,	..	..	
22	Painting doors and windows with chocolate silicate paint	Sqr.	4 8 0	8·20	
23	Providing and fixing rain water zinc or C. I. spouts	L. S.	..	..	
24	Providing water supply connections ..	,,	..	..	
25	Providing Electric light connections	,,	..	..	
26	Constructing a set of latrines and urinals with stone in surki mortar and cement pointing ..	,,	..	..	
27	Constructing a compound wall alround with gate way	,,	..	..	

P. SUBBA RAO,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 31st December 1937.

The attention of the public is invited to the Notification published in pages 11-12, Part VI of the *Mysore Gazette*, dated 6th January 1938, calling for tenders for the construction of a block of 5 units for Line Mines Quarters at Lingadahalli, Tarikere Taluk.

The last date of receipt of tender in this office is 24th January 1938.

Abstract Notification dated 1st January 1938.

The attention of the public is invited to the notification published in pages 12-13, Part VI of the *Mysore Gazette*, dated 6th January 1938, calling for tenders for the work of Constructing a High Level Causeway across the Halla near Mudgere Pumping Station on Belur-Mudgere Road.

The last date of receipt of tender in this office is 24th January 1938.

C. R. IYENGAR,
Executive Engineer.

ANJANAPUR DIVISION.

Notification dated 9th January 1938.

The following list of arrears outstanding in the Divisional Accounts against the labour and piece workers of Anjanapur Division, is hereby published for the information of the parties concerned. The claimants, if any, should prefer their claims within 3 weeks from the date of this Notification for needful, after which period no claims will be entertained and the amount will be forfeited to Government.

Statement of arrears outstanding in the Divisional Accounts against the labourers and piece-workers.

Sl. No.	Name	Amount	Sl. No.	Name	Amount
		Rs. a. p.			Rs. a. p.
1	Sannappa Nagaral	0 15 0	46	Shimoga Mariya	1 5 0
2	Jummanna Iddalgi	0 7 0	47	Shimoga Fakeerappa	1 5 0
3	Giddavva Basappa	0 10 0	48	Naranappa	0 7 0
4	Yelehanka Gidda	0 14 0	49	Jamal Sab	0 4 0
5	Timma Dasa	0 10 0	50	Thimma Mariappa	0 8 0
6	H. Kasnya	0 7 0	51	Hanumappa Giddappa	0 8 0
7	Timmavva Mallappa	0 4 0	52	Venkappa Bhimmappa	0 7 0
8	Bhuggi Thimma	0 5 0	53	Basappa Belgal	0 14 0
9	Thimmanna Dhyamanna	0 3 0	54	K. Lochamma	0 5 0
10	Basavva Dharmanna	0 4 0	55	Mattghatta Hanumantha	0 7 0
11	Setya (boy)	0 2 0	56	Yamunappa Hasanappa	2 0 0
12	Hubballi Thimma	0 4 0	57	Ramaboyee	0 7 0
13	Malla Hanaval	0 14 0	58	Bhimavva Hippargi	0 4 0
14	Sivappa Hanumappa	0 2 0	59	Rajamma	0 4 0
15	Hereballi Kasim Sab	0 2 0	60	Amruhur Narasa	1 0 0
16	Basavva Hanumanna	0 3 0	61	Agimakarani	0 8 0
17	H. Dodda Lali	0 4 0	62	Basya Ramanna	0 4 0
18	Somaiya	1 5 0	63	Deen Mahamad	0 15 0
19	Ramappa Mudukappa	0 8 0	64	Gampal Nagaiya	1 5 0
20	C. Raman	0 12 0	65	Hanumantharaya Chennapatna	1 12 0
21	Hanumappa Karibasappa	0 5 0	66	Mathighatta Era	0 4 0
22	Hanumavva Bhimavva	0 4 0	67	H. Kadri	0 4 0
23	Yamunappa Ali Chand	0 6 0	68	H. Dodda Lemali	0 4 0
24	Mavanoor Nanja	0 6 0	69	Bellavi Hanumantha	0 11 0
25	Hassan Nanja	0 6 0	70	Belgaum Nagamma	0 14 0
26	Durgappa	0 7 0	71	Belgaum Yellamma	0 8 0
27	Basappa Chittargi	0 7 0	72	Thimmavva	0 3 0
28	Dasanna Chittargi	0 7 0	73	Ramavva	0 3 0
29	Dasa Jallegowda	0 8 0	74	Phakeerappa	1 0 0
30	Bhimappa Kannahalli	0 7 0	75	Pulyavva	0 3 0
31	A. Krishna	4 0 0	76	B. Hanumantha	0 4 0
32	Voddara Hanumappa	0 4 0	77	Kenchavva	0 2 0
33	Thimmavva Mudukappa	0 12 0	78	Baladandappa	1 0 0
34	Doddajogihally Kasnya	0 7 0	79	Sangavva Thimmavva	0 4 0
35	Latchi	0 4 0	80	Hanumiah, K.	0 7 0
36	Sivani Setyamma	0 2 0	81	Bhima Thimmiah	4 8 0
37	Kalakappa Mallappa	0 7 0	82	Allahalli Yellappa	0 4 0
38	Chitnahally Papanna	0 7 0	83	Hanumavva Phakeerappa	0 5 0
39	Eraiya Nagamangala	0 7 0	84	H. Rama	0 4 0
40	Shimoga Bhimappa	0 14 0	85	Krishna	2 8 0
41	Pakeer Sab	0 14 0	86	Pujari Seviya	0 4 0
42	Muddiah Nagamangala	0 15 0	87	Pujari Rama	0 4 0
43	Hutchaiya Nagamanga	0 15 0	88	Jogihally Eria	0 4 0
44	K. Rama	1 0 0	89	Jogihally Thakria	0 4 0
45	Lakkappa Chittargi	1 6 0	90	Jogihally Naik Rama	0 4 0